

FOR HIRE OR SALE

Fairey 2.5 Tonne Tug Winch



Specifications

- Single axle "A" frame drawbar trailer fitted with 185x14 wheels & tyres.
- Full overrun braking system and Handbrake.
- Fully enclosed bodywork, all panels removable.
- Twin Capstan Winch Unit. (50 Mtrs/Min No-Load. 10 Mtrs/Min Full-Load.)
- Separate Rope Storage Unit, 500 Metres (Standard) or 1000 Mtr (Option).
- 8mm diameter wire rope 6x 19 IWRC construction.
- Lombardini FOCS (Model 1003) water-cooled diesel engine.
- High capacity variable displacement main pump (capstans).
- Fixed displacement secondary pump (rope storage).
- Automatic throttle when winching In-Out.
- Four adjustable corner support legs.
- Infinite rope speed control.
- Pre-set tonnage control.
- Actual tonnage readout gauge.
- Emergency Stop.
- Emergency shutdown protection
- Hour run meter.
- Full Road Lighting (optional).

Please request any options not mentioned, we probably do them anyway.

(SEE SEPARATE SHEET FOR BOOM KITS.)

UNDERGROUND SYSTEMS LIMITED
Sunderland Road, Sandy. Beds SG19 1RS. Tel: 01767-691414. Fax: 01767-683914